Groundwater
Basin
Remediation
in the City of
Los Angeles

September 28, 2016
Groundwater Resources
Association Conference
Concord, CA



Evelyn Cortez -Davis, P.E.
Los Angeles Department of Water & Power
Manager of Groundwater Planning

Agenda

Background

Program Approach

Remediation Projects

Funding

Next Steps

City of Los Angeles Overview

About 4 million residents


473 square-miles

LADWP: Largest municipal utility in U.S.


681,000 service connections

550,000 Acre-feet/year served

7,300+ miles of water pipes




Water Sources and Reliability Challenges




2015 Urban Water Management Plan

Fiscal Year 2011-15 Average Total: 550,130 AFY


Fiscal Year 2039-40 Average Total: 675,700 AFY



Allocated Water Rights



Background



Site Characterization

\$33.5 M


Characterized basin

- 6-year study (2015)
- Identified contaminants
- 70,000 data points

New Monitoring Wells

26 Monitoring Wells

Updated 1992 Remedial Investigation



Community Involvement

Site Characterization

High Priority Contaminants

Volatile Organic Compounds


- TCE
- PCE
- 1,1 DCE
- cis-1,2DCE
- 1,2 DCA
- Freon 11
- CTET

Inorganic Compounds

- Chromium
- Perchlorate
- Nitrate

Other Chemicals

- NDMA
- 1,2,3 TCP
- 1,4-Dioxane



Agenda

Background


Program Approach

Remediation Projects

Funding


Next Steps

Program Approach



Overall Goal: Basin Remediation

General Approach for Remediation Projects



Program Key Term Definitions

- Preferred Wells
 - Wells that do not show current contamination.
- Secondary Wells
 - Wells with contamination levels below MCLs/NLs.
- Remediation Wells
 - Contaminated wells that require treatment.

Agenda


Background


Program Approach

Remediation Projects

Funding

Next Steps





North Hollywood Central Treatment Facility*


Type of Proposed Treatment: Aeration with LPGAC And VPGAC for Volatile Organic Compound (VOC) Treatment

Design/Build Timeframe: Late 2017 – June 2021

Progressive Design-Build

Treatment Components

- Aeration Towers
- Liquid Phase Granular Activated Carbon (LPGAC)



Tujunga Central & Wellhead Treatment Facilities*

Type of Proposed Treatment: Aeration with LPGAC & VPGAC for VOC and AOP for 1,4-Dioxane

Design/Build Timeframe: Late 2017 – June 2021

Progressive Design-Build

Treatment Components


- Aeration Towers
- LPGAC
- VPGAC
- AOP (UV/H₂0₂)




^{*} Pending completion of Feasibility Study

Preliminary Tujunga PCE Plume Modeling: Year 30 (Preferred Wells Pumped First)


Particle Tracking







Preliminary Tujunga PCE Plume Modeling: Year 30 (Remediation Wells Pumped First)

Particle Tracking







North Hollywood West Wellhead Treatment Facility*

Type of Proposed Treatment: 1,4-Dioxane Treatment using AOP

Construction: September 2017 – December 2019

LADWP's Power Construction & Maintenance group.

Treatment Components

- AOP (UV/H₂0₂)
- LPGAC


Proposed Site

VANCOURANT

VAN

^{*} Pending completion of Feasibility Study

Proposed NHW Treatment*



^{*} Pending completion of Feasibility Study

Pollock Wellhead Treatment Facility*

Type of Proposed Treatment:

1,4-Dioxane (and possible Chromium) Treatment using AOP

Construction: September 2018 – December 2020

LADWP's Power Construction & Maintenance group.

Treatment Components

- AOP (UV/H₂0₂)
- LPGAC
- Potential Chromium Treatment

SCE T/L TOWER
No. 1772791E

SCE T/L TOWER
No. 2184548E

FWY WEST BOUND
OFF-RAMP

ROUTE 2

^{*} Pending completion of Feasibility Study

Agenda

Background

Program Approach

Remediation Projects

Funding

Next Steps


Funding Sources

- Water Rates
- Responsible Parties
- Proposition 1
 - > Round 1 final apps due Fall 2016
 - Grant program (50% local match)
 - Must be operational by June 2021
- Securitization
- Other State/Federal programs


Preliminary Capital Cost \$635M (BEING REVISED)



Program Schedule



Program Schedule



Agenda

Background

Program Approach

Remediation Projects

Funding

Next Steps

Next Steps

Complete Groundwater Modeling NCP & CEQA/NEPA Regulatory Permitting Process Complete Scope of Work Documents Begin Design

